CHITALDRUG DIVISION.

Abstract Notification.

The attention of the public is hereby invited to the advertisement on page Nos. 15 to 16 of Part VI of the *Mysore Gazette*, dated 5th January 1933, calling for tenders for constructing the Muslim Hostel at Davangere, Chitaldrug District.

R. TIPPAIYA,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

OFFICE OF THE CHIEF ELECTRICAL ENGINEER IN MYSORE, BANGALORE.

Constructing Electrical Buildings at Chintamani Town.

Attention is invited to notification, dated 19th December 1932 published in pages 1492 to 1495, Part VI of the *Mysore Gazette*, dated 22nd December 1932 calling for tenders for the above works. The latest date for tenders is 20th January 1933.

C. M. CARIAPA,
Chief Electrical Engineer.

Notification dated 5th January 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Chief Electrical Engineer, Bangalore, up to 2 P.M., on the 27th January 1933, for constructing one block of quarters with latrine at Malavalli Town.

1. The tenders will be opened in public at 2 P.M., on 27th January 1933. The work should be completed within three months and the monthly progress should not be less than Rs. 800.

2. The plan, detailed estimates and the conditions may be seen at the Office of the Chief Electrical Engineer, Bangalore, on all working days during the office working hours.

3. The tenders should be accompanied by a statement in the form attached showing the rates at which different items specified will be executed. The rates should be in figures as well as in words.

4. Each tender must be accompanied by a deposit of Rs. 200 in Government Promissory Notes as earnest money and be superscribed "Tender for constructing a block of quarters at Malavalli."

5. The final acceptance of any tender will rest with the Chief Electrical Engineer who does not bind himself to accept the lowest or any tender or to assign any reasons whatever for the rejection of any tender. The Chief Electrical Engineer also reserves the right to accept or reject any portion of the tender.

6. Within eight days of the award of the tender, the successful tenderer will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful tenderer will be posted on the notice board of the Chief Electrical Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The construction work should be started within a week from the date of notification of acceptance.

10. Water for construction should be got at the contractor's own expense.

11. Specifications for works are those recognised by the Mysore Public Works Department and Marroyt's specifications.

12. The contractor should be bound by the conditions of the schedule of contract of the Electrical Department.

Statement showing the approximate quantities of work for constructing one block of quarters with a block of latrines at Malavalli.

Sl. No.	Description of item	Unit	Quantity in	
			Quarters	Latrine
1	Earthwork excavation including filling in basement.	C.yd.	44	4
2a	Concrete stone jelly in ordinary mortar ...	C.ft.	347	..
b	Coursed rubble stone masonry in clay, foundation and basement, including through stones at six feet intervals in every course.	"	986	130
c	Burnt brick in clay superstructure	"	2,070	..
d	Do in mortar do	"	352	196
e	Stone slabs 4" thick roughly dressed and fixed in mortar.	S.ft.	156	...
f	Stone pillars 4" thick including paly cutting and fixing in position.	"	26	..
g	Plain cornice 6" projection built of brick in mortar and chunam plastered complete.	R.ft.	75	...
h	Chunam plastering two coats	Square	52·16	4·91
i	Pointing with chunam mortar including thread lines.	"	1·00	0·56
j	White and colour washing, two coats	"	53·16	5·47
k	Binding wall $1\frac{1}{8}$" x $\frac{3}{4}$" brick in mortar and chunam plastered and white washed. ...	R.ft.	74	...
l	Chunam borders 6" x 3" over varandah roof ...	"	30	...
3	Flooring with 3" concrete and cement plaster $\frac{1}{4}$" thick well trowelled and finished smooth and even.	Square	8·20	...
4a	Roofing with 1st Class Mangalore tiles on teak reepers including wood oiling to reepers.	"	11·81	...
b	Ridge tiles set in mortar and cement pointed ...	R.ft.	23	...
c	Ventilating tiles set in mortar	each	16	...
d	Mattywood work with wood oiling, two coats ...	C.ft.	41·50	...
e	Doors, teak wood frames with honne wood battened 1" thick shutters with fittings, etc., complete.	S.ft.	78	...
4f	Windows with teak wood frames and honne wood battened shutters 1" thick with iron bars 5/8" dia. and necessary fittings, etc., complete.	"	70	...
g	Ventilators with teak wood and glazed shutters fixed complete.	"	24	...
h	Chocolate painting, two coats	Square	3·55	...
i	Constructing sinks with drain pipes complete ...	Each	4	..
j	Providing stone mortar and pestle including fixing...	"	4	...
k	Galvanized iron sheet sun shade on teakwood battens with chocolate painting.	"	4	...
5	Flooring with 3" concrete bed with cement plastering $\frac{1}{2}$" thick on top.	Square	...	0·38
6	Cement plastering $\frac{1}{2}$" thick	"	...	0·79
7	Tar washing two coats ...	"	...	0·63
8	Fixing outlets from the latrine with drains complete.	1 item	...	Lump sum.
9	Providing galvanized iron sheet tubs 12" x 6" with handles, etc., complete with tarring	Each		6

V. R. COWSIK,
For *Chief Electrical Engineer.*

OFFICE OF THE DIRECTOR OF AGRICULTURE IN MYSORE, BANGALORE.

Notice No. Roc. 1382—*Sc.* 134 *of* 32-33, *dated* 26*th December* 1932.

Sealed tenders will be received in the office of the undersigned up to 12 noon on Friday the 27th January 1933 for the supply of spraying materials for the Mysore Agricultural Department.

For further particulars, please see page 19, Part VI of the *Mysore Gazette*, dated 5th January 1933.

K. BHIMA RAO,
For *Director of Agriculture.*